

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-185-30198-0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Leo G. Wetherill Jr.

Complete Address: 2208 Power & Light Bldg., Kansas City, Mo.

Lease Name: Spangenberg Well No. # 1

Location: SE SE NW Sec. 33 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3700' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Curtis was instructed to plug the well as follows:

238' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 225', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement  
with 10 sacks to base cellar. Bridge and cement rat hole with  
2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

APR 23 1965

Archie Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas