

Jo

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 35-19

LOCATION NE-SW-NE

SEC. 36 TWP. 22 RGE. 14-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Hart

Operator Musgrove Petro. Corp. Address 407 K.F.H. Bldg. Wichita-Kans.

Field _____ County Stafford

Total Depth 3851 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 314 ft. Circulated with cement
5 1/2" casing set at 3690 ft. Cemented with 100 sacks cement.
Low Wells Plug at 3670 ft. Chat from 3670 to 3515 ft -
Runned 6 sacks of cement at 3515 ft. Shot off & Pulled
the 5 1/2" casing. Mud to 314 ft. Set Arch Bridge &
15 sacks of cement at 314 ft. Mud to 30 ft. Plug
& 10 sacks of cement at the surface.
Mr. Arnett - Plugging Contractor

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 27 1950
 CONSERVATION DIVISION
 Wichita, Kansas

10-27-50

C. D. Stough
 District Conservation Agent

Date 10-28-50

PLUGGING
 FILE SEC. 36 TWP. 22 R. 14
 BOOK PAGE 35 LINE 19