

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-20319-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Vincent Oil Corporation

Complete Address 1110 K.S.B + T Building 125 N. Market, Wichita, Ks 67202

Lease Name Francy - Schrag Well No. 1

Location 1120' FNW 990' FEL NW-4 Sec. 26 Twp. 22 Rge. 3 (~~East~~)(West)

County Harvey Total Depth 3250'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling

Address Chase, Ks, License No. 683

Operation Completed: Hour: 3:15 pm Day: 6 Month: May Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

Perf 3234-37 3221-25 3169-76 Perf plugged off w/50 rks  
cmh, plug displaced, line run 24 hrs later, tagged @ 3102'.

Allied cnty ticket # 28247. Pipe pulled, high fluid level.  
plugged w/5 shells, 10 gel, 150 rks 50 Poz 37cc. 27 gel  
max Pres 500#, shut in @ 500#. Allied Cnty ticket # 29734.

4 1/2" @ 3249' w/100 rks

Recovered: 2247' of 4 1/2" Casing

Amount of Surface Casing: 10 3/4" @ 201' w/250 rks

RECEIVED  
STATE CORPORATION COMMISSION

5-17-82 MAY 17 1982

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Merlaw W. Unruh  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Bottom witnessed by Don Thompson - Eldorado. I was @ 15-13-6E -  
15-061-20033. In Wichita office when top was plugged, with  
Jim Schief discussing problem 25-18-4W.

Signed: Merlaw W. Unruh  
Conservation Division Agent

INVOICED

DATE 5-24-82

INV. NO. 1785-E