

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1979

6-27-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-145-20.380 (of this well)

Operator's Full Name RICE ENGINEERING & OPERATING, INC. (Bell Brothers)

Complete Address 1020 HOOVER - GREAT BEND, KANS. 67530

Lease Name H.-D. EDDY Well No. # 1-"A"

Location NW-SE-NE Sec. 14 Twp. 22 Rge. 18 (E) (W) W

County PAWNEE Total Depth 4250 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor KELSO CASING PULLING

Address BOX 176 CHASE, KS. 67524 License No. 683

Operation Completed: Hour 2:35 ^{PM} Day 23 Month JUNE Year 79

The above well was plugged as follows:

8 5/8 275' S.B. CWC 260 ST 60 ST 30 Perm - 5 1/2 4250 ^{FE} CWC. 150 ST SAND SET.

T.D. 4250 ^{FE} PERF. 4082 ^{FE} TO 4085 ^{FE} - PLUG BACK AT 4124 ^{FE} BY

SAND AND 5 ST CMT. TO 4050 ^{FE} SHOT PIPE AT 2080 ^{FE}

RECOVERED 1957 ^{FE} LEFT 123 ^{FE} OF 5 1/2" AT TOP OF SURFACE

BECAUSE OF FLOW. - USED APPROX 200 ST OF GEL-T HEAVY MUD TO

STOP FLOW WHILE PULLING CASING.

PUT IN 140 ST COMMON 3% CA-CL. THROUGH 5 1/2"

AND CIRCULATED ANNULUS. CEMENTED BY ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

Signed: Marvin Schmidt
Well Plugging Supervisor

INVOICED.
DATE 6-27-79
INIV NO. 9912-W