



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-SW-NE

SEC. 14 TWP. 22 RGE. 18-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Fisher Fischer

Operator Crown Oil Co. Address S. Bend. Kans.

Field _____ County Stafford Co

Total Depth 3770 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 314 ft. Circulated with cement.
5 1/2 casing set at 3770 ft. Cemented with 15 sacks of
cement. Plugged back to 3150 with Lane Wells
Plug & shot. Dumped 5 sacks of cement at 3150 ft.
Shot off & pulled the 5 1/2 casing - mud to 300 ft.
Set Rock Bridge & 15 sacks of cement at 300 ft.
Mud to 30 ft - Plug & 10 sacks of cement at
the surface

RECEIVED
STATE CORPORATION COMMISSION

4-18-51

PLUGGING
FILE SEC. 14 T. 22 R. 13W
BOOK PAGE 74 LINE 35

APR 18 1951

C. M. Stough
District Conservation Agent

Date 4-16-51

F