

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 19 1964  
 5-19-64  
 CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Howard Ward of Tommy Ward Drilling Co. has this

date requested permission to plug the following described well:

Mr. Ward guarantees payment of the plugging fee.Operator's full Name: Woody's Quality Oil CompanyComplete Address: 1119 Cravens Bldg., Oklahoma City, OklahomaLease Name: Fisher Well No. # 1Location: NE Sec. 14 Twp. 22 Rge. 13 (E) (W) WCounty Stafford Total Depth 3850 Oil WellGas Well    Input Well    SWD Well    D & A X Lost Hole   Mr. Ward was instructed to plug the well as follows:

250' of 8 5/8" surface pipe, cemented with 250 sacks. Fill  
hole with drilling mud to 240', 1s cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent