

State of Kansas



15-155-20376-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

April 18, 1977

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 27 1977

CONSERVATION DIVISION  
Wichita, Kansas

4-27-77

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Dick Mead of Sterling Drilling Co. has this date requested permission to plug the following described well:

Mr. Mead guarantees payment of the plugging fee.

Operator's full Name: Doskacil Sausage Company

Complete Address: 321 N. Main, South Hutchinson, Kansas

Lease Name: Culver Well No. 1

Location: 450' FWL 330' FSL SW/4 Sec. 6 Twp. 22 Rge. 9 (E)(W) X

County: Reno Total Depth 3177' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Mead was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 200'.

Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks cement.

Very truly yours,

Richard J. Tomer  
Conservation Division Agent