

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

September 28, 1963

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

OCT 7 1963  
10-7-63

Dear Sir:

Mr. Oliver Kemp of Lario Oil & Gas Company <sup>has this</sup> <sub>Wichita, Kansas</sub>

date requested permission to plug the following described well:

Mr. Kemp guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 So. Market, Wichita 2, Kansas

Lease Name: Haltom Well No. 1

Location: NE NE SE Sec. 6 Twp. 22 Rge. 9 (E) (W) X

County Reno Total Depth 3730' Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Kemp was instructed to plug the well as follows:

Push 5½" plug to 3360'. Fill hole with sand to 3350' and  
cement with 5 sacks. Fill hole with mud to 250'. Set  
rock bridge from 250' to 240' and cement with 20 sacks.

Fill hole with mud to 40'. Set rock bridge from 40' to 30'.

Cap hole with 10 sacks cement.

Very truly yours,

*[Signature]*  
Conservation Division Agent