

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

October 2, 1963

RECEIVED  
 STATE CORPORATION COMMISSION

OCT 10 1963

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this

date requested permission to plug the following described well:

Mr. Ralph Glenn guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 So. Market, Wichita, Kansas

Lease Name: Haltom Well No. 2

Location: C NW SE Sec. 6 Twp. 22 Rge. 9(E) (W) X

County Reno Total Depth 3648' Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Glenn was instructed to plug the well as follows:

Push 4½" plug to 3600'. Fill hole with sand to 3590' and  
cement with 3 sacks. Fill hole with mud to 220'. Set  
rock bridge from 220' to 210' and cement with 20 sacks.  
Fill hole with mud to 40'. Set rock bridge from 40' to  
30' and cap hole with 10 sacks cement.

Very truly yours,

*Arthur J. Loren*  
 Conservation Division Agent