

15-185-10907-0000

Form CP-3
Rev. 6-26-62

KANSAS

14
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-20-66

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tom-Kat, Inc.

Complete Address: 1127 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Soeken "A" Well No. # 1

Location ~~S/2 SW NW~~ *S/2 SW NW* Sec. 20 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3858'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:00PM Day 11th Month June Year 1966

The Above well was plugged as follows:

332
257' of 8 5/8" surface pipe, cement circulated. 3650' of 5 1/2" long string,
with the cement at 3170'. This is an open hole. Bottom of the hole was
sanded to 3625', and cemented with 5 sacks, through the dump bailer.
2820' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 250', rock bridge from 250' to 240'. 5 sacks of cement
was mixed in a barrel, and put on plug at 240', through the dump bailer,
and let set over-night. Next day hole was bailed dry and 20 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 6/20/66

INV. NO. 3407-W