

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 17 1974

CONSERVATION DIVISION
Wichita, Kansas

4-17-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Messman-Rinehart Oil Co

Complete Address 1432 Wichita Plaza Wichita, KS

Lease Name Brodie Trust Well No. 1

Location SW/SE/SW Sec. 27 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3750

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 9:00 AM Day 16 Month 4 Year 1974

The above well was plugged as follows:

346 ft 8 5/8 surface cement circulated. 3700 ft 4 1/2 long string
cemented with 100 sacks. Top per. 3619 ft. Sand to 3600 ft, 4 sacks
cement with bailer. Pulled 1920 ft 4 1/2. Pump 3 sacks hulls, 15 sacks
gel, 125 sacks cement to surface.

Pumped by Allied Cementing Co. Great Bend, KS

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/17/74

INV. NO. 8940-W