

15-185-30194-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

RECEIVED
STATE CORPORATION COMMISSION

DEC - 1 1965

CONSERVATION DIVISION
Wichita, Kansas

12-1-65

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Cossman Well No. # 1

Location NW SW NW Sec. 28 Twp. 22 Rge. 13 (E) W

County Stafford Total Depth 3522'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 12:00PM Day 28th Month Nov. Year 1965

The Above well was plugged as follows:

303' of 8 5/8" surface pipe, cement circulated. Fluid was up in the
hole. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to
290', and cemented with 25 sacks, through the drill pipe. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged solid
with dry cement and hulls on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12-1-65

INV. NO. 2309-W