

15.053.00020.00.00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 136-4

LOCATION W 1/2 - NW - NE

SEC. 7 TWP. 17 RGE. 10W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Frewert

Operator Drillers Prods. Co. Inc Address 208 Ins. Bldg. 212 N. Market St
Wichita Kans.

Field _____ County Ellsworth

Total Depth 3404 1/2 Feet.

Plugging Contractor West Supply Co.

Plugging Contractor's License No. # 14

Address Chase, Kans

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8" Φ 276' C.W.C. 5 1/2" Oil string
was set at 3381 1/2 with 75 SX of Cem. Filled hole back
with sand to 3370 and dumped 5 SX of Cem. with
dump trailers shot off and pulled 5 1/2" casing. Filled
hole with mud to 250' set 10' rock bridge and
dumped 20 SX of Cem. with trailers. Filled hole
with mud to 40' Rock bridge and 10 SX of Cem. to
surface. Well complete

Warrens J. Harner
District Conservation Agent

Date 10-23-53

10-27-53

PLUGGING
FILE SEC. 7-T-17R-10W
BOOK PAGE 136 LINE 4

RECEIVED
CONSERVATION
SECTION
OCT 27 1953