

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER. 15-185-20158-0000

LEASE NAME Spatz

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
 SW NE SE

SEC. 26 TWP. 22S RGE. 13W (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 2-9-88

Plugging Completed 2-17-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR W.L. Kirkman, Inc.

ADDRESS P.O. Box 782290
 Wichita, Kansas 67218-2290

PHONE#(316) 685-5372 OPERATORS LICENSE NO. 5673

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3754'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	262'	none
				5-1/2"	3747'	2571'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3680' and 5 sacks cement. Set pipe @3030', 2805' 2571', pulled a total of 78 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 8-5/8" plug and 125 cement, 60/40 pos, 6% gel.

Plugging Complete
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 2-22-88

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 88

Jane Hoover
 Notary Public

My Commission Expires:



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

SPAATZ #1
 SW NE SE Section 26-22S-13W
 Stafford County, Kansas

Commenced: February 4, 1969
 Completed: February 14, 1969

OPERATOR - Wayne Kirkman

DEPTH		FORMATION	REMARKS
From	To		
0	186	Surface clay and sand	
186	230	Sand	
230	262	Red bed	Ran 7 joints of 8-5/8" casing, set @ 262' w/240 sacks cement.
262	700	Shale	
700	1260	Shale and red bed	
1260	1785	Shale and shells	
1785	1915	Lime	
1915	3300	Lime and shale	
3300	3475	Lime	
3475	3535	Lime and shale	
3535	3754	Lime	
3754	TD		Ran 116 joints of 5-1/2" casing, set @ 3747', 7' off bottom, w/85 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the SW NE SE Section 26-22S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

E. E. Hall

E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 13 1969

Before me, the undersigned, a Notary Public within and for said County and State, on this 18 day of February, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
 Barbara J. Layton, Notary Public

