

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 27 TWP. 22s RGE. 13W E/W
Location as in quarters or footage from lines:
NW NW SW

Lease Owner L.D. Drilling, Inc.

Lease Name Soeken #1 Well No. _____

Office Address Box 324 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 11-6-81

Plugging completed 11-11-81

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3901'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	305'	none
				4-1/2"	3900'	2811'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3525' and set 4 sacks cement. Shot casing @2815' and pulled a total of 73 joints of pipe. Plugged well with 25 sacks gel, 4 sacks hulls, 8-5/8" plug, 150 sacks 50/50 pos, 2% gel, 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18TH day of November, 19 81

My Commission expires: _____



Irene Hoover
RECEIVED Notary Public.
STATE CORPORATION COMMISSION

NOV 20 1981

11-20-81

CONSERVATION DIVISION
Wichita Kansas

DRILLERS WELL LOG

L. D. DRILLING, INC.

- CONTRACTOR

ROCKWOOD PETROLEUM, INC. - OPR.

SOEKEN # 1
 NW NW SW
 Sec. 27-22S-13W
 STAFFORD COUNTY, KS.

T. D. 3901
 ELEV. 1906 K.B.

COMMENCED: 5-14-81
 COMPLETED: 5-21-81

CASING:

8 5/8" set at 305'
 4 1/2" set at 3900' (1' off bottom)

FORMATION:

W/280 sx. 50/50 Pozmix, 2% gel, 3% CC
 W/175 sx. Cement, 18% Salt Sat.

FORMATION

Sand
 Sand & shale
 Red Bed
 Anhy.
 Shale W/shells
 Lime & Shale & Arb.
 R.T.D.

DEPTH

0-260
 260-310
 310-759
 759-783
 783-1620
 1620-3901
 3901

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 20 1981
 CONSERVATION DIVISION
 Wichita, Kansas

FORMATION TOPS:

LOG

Anhy.	759-783
Heebner	3284
Toronto	3305
Brown Lime	3417
Lensing K/C	3438
Base K/C	3660
Viola	3746
Simpson Shale	3798
Simpson Sand	3817
Arbuckle	3842
R.T.D.	3901

AFFIDAVIT

State of Kansas)
) ss
 County of Barton

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Popp

 Don Popp

Sworn to and subscribed before me this 3rd day of June, 1981.

My appointment expires: 5-20-85

Bessie M. DeWerff

 Bessie M. DeWerff, Notary Public

