

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
205 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20,851-0001

LEASE NAME McMillan

WELL NUMBER #1 (OWWO)

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 27 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-14-89

Plugging Completed 1-19-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Grady Bolding Corporation

ADDRESS Box 244, Great Bend, Kansas 67530

PHONE# (316)-564-2765 OPERATORS LICENSE NO. 7383

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 10, 1989 (date)

by Duane Rankin and Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3871'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put in	Pulled out
			8-5/8"	298'	None
			4-1/2"	3870'	2,780.55'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3500' and 4 sacks cement. Shot casing at 2750'. Pulled 68 joints of 4-1/2" casing. B.J. Titan plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 120 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 400 psi and shut in 250 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold  
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 19th day of January, 1989

Jona M. Leatherman  
Notary Public

My Commission Expires:

