

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15,185-21,298-0006

LEASE NAME McMillan

WELL NUMBER #5

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2870 Ft. from S Section Line

5050 Ft. from E Section Line

SEC. 27 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Grady Bolding Corporation

ADDRESS Box 244, Great Bend, Kansas 67530

PHONE# (316)-564-2765 OPERATORS LICENSE NO. 7383

Date Well Completed \_\_\_\_\_

Character of Well oil

Plugging Commenced 7-18-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-16-89

The plugging proposal was approved on August 13, 1989 (date)

by Duane Rankin and Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, Is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	306'	None
				4-1/2"	3689'	2,186.00'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. Dumped sand to 3410' and 5 sacks cement. Shot casing at 2800', 2500' and 2200'. Pulled 52 joints of 4-1/2" casing. B.J. Titan plugged with 400# hulls, 10 sax gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 400 psi and shutin 200 psi.

8-18-89

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation AUG 18 1989

STATE OF Kansas COUNTY OF Barton, ss.

CONSERVATION DIVISION  
Wichita, Kansas

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filled that the same are true and correct, so help me God.

(Signature) James W. Rockhold


James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1989

Iona M. Leatherman  
Notary Public

My Commission Expires:



## DRILLER'S WELL LOG

DATE COMMENCED: 05/18/81  
 DATE COMPLETED: 05/23/81

Allen Drilling Company  
 McMILLAN Well No. 5  
 100'S & 100'W of SW SW NW  
 Sec. 27, Twp. 22S, Rge. 13W,  
 Stafford County, Kansas

ELEVATION: G.L.  
 K.B.

## FORMATION DATA:

No geologist

## SURFACE PIPE:

Ran 7 jts new 20# 8-5/8"  
 casing, tally: 299';  
 Set @ 306' w/ 290 sks 60/40  
 poz., 2% gel, 3% c.c.  
 cement circ., plug down  
 9:15PM, 5/18/81 By Howco

## PRODUCTION PIPE:

Ran 88 jts. 4½" 9½# casing  
 Tally: 3912'; Set @ 3689'  
 w/ 100 sks quik-set, plug  
 down 8:30 AM, 5/23/81  
 By Dowell

RECEIVED  
 STATE CORPORATION COMMISSION

6 1989  
 CONSERVATION DIVISION  
 Wichita, Kansas

## A F F I D A V I T

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

Greg Davidson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best