

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15,185-21,294-0000

LEASE NAME McMillan

WELL NUMBER #4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3430 Ft. from S Section Line

5050 Ft. from E Section Line

SEC 27 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Grady Bolding Corporation

ADDRESS Box 244, Great Bend, Ks. 67530

PHONE # (316)-564-2765 OPERATORS LICENSE NO. 7383

Date Well Completed _____

Character of Well oil

Plugging Commenced 8-5-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-16-89

The plugging proposal was approved on August 14, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	324'	None
				4-1/2"	3699'	2,218.36'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3400' and 4 sacks cement. Shot casing at 2800' 2500' and 2200'. Pulled 53 joints of 4-1/2" casing. B.J. Titan plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 450 psi and shutin 200 psi.

8-18-89

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

RECEIVED

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Grady Bolding Corporation

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

AUG 18 1989

James W. Rockhold

(Employee of Operator) OR (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1989

Jona M. Leatherman
Notary Public

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

My Commission Expires:

DRILLER'S WELL LOG

DATE COMMENCED: 05/13/81
DATE COMPLETED: 05/18/81

Allen Drilling Company
McMILLAN No. 4
100'W, 260'S NW SW NW
Sec. 27, Twp. 22, Rge. 13W,
Stafford County, Kansas

ELEVATION: G.L.
K.B.

FORMATION DATA:

No geologist

RECEIVED
STATE CORPORATION COMMISSION
6 1989

CONSERVATION DIVISION
Wichita, Kansas

SURFACE PIPE:

Ran 8 jts. 20# new 8-5/8"
casing; tally: 317'; Set @
324' w/ 280 sks 60/40 poz.,
2% gel, 3% cc., cement circ.
Plug down 11 PM, 5/13/81
By Halliburton

PRODUCTION PIPE:

Ran 88 jts. 9.5# 4-1/2"
casing; tally 3707';
Set w/ 100 sks 50/50 poz.,
Plug down 7 AM, 5/18/81
By Halliburton

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Greg Davidson , of lawful age, does swear and state that the
facts and statements herein contained are true and correct to the best