


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Stafford County. Sec. 28 Twp. 22S Rge. 13 (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Beardmore Drilling Company  
Lease Name Searle Well No. 1  
Office Address 603 Petroleum Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 8 1953  
Application for plugging filed August 7 1953  
Application for plugging approved August 7 1953  
Plugging commenced August 8 1953  
Plugging completed August 8 1953j  
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3890 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Sand and Clay		0	290	8-5/8"	290	--0--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from top feet to bottom feet for each plug set.

Heavy Mud from 270' to 3890'

Wood Plug @ 270'

20 Sacks Cement 210' to 270'

Heavy Mud from 35' to 210'

Wood Plug 35'

10 Sacks Cement surface to 35'

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 18 1953  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Beardmore Drilling Company  
Address 603 Petroleum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, HEBER BEARDMORE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore  
603 Petroleum Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 19 53

Leonard P. Tolle  
Notary Public.

My commission expires January 28, 1956

PLUGGING  
FILE SEC 28 T 22 R 1300  
BOOK PAGE 120 LINE 43

SEARLE NO. 1

NE NE NE  
Section 28-22S-13W  
Stafford County, Kansas

Drilled for: Kiowa, Derby & Beardmore  
Drilled by: Beardmore Drilling Company

## Casing Record:

8-5/8" 290<sup>+</sup> w/225 Sacks

Drilling Commenced: July 29, 1953  
Drilling Completed: August 8, 1953

Elevation: RB 1903  
GR 1897  
DF 1900

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	5
Sand	260
Red Rock, Shale - Shells	290
Shale - Shells - Red Rock	765
Anhydrite	790
Shale - Shells	1590
Shale - Lime	1935
Lime	2215
Lime - Shale	3220
Lime	3777
Lime - Shale	3830
Lime	3891 T. D.

D &amp; A

TOPS:

Anhydrite	764
Tarkio	2675
Topeka	2972
Heebner	3282
Toronto	3303
Brown Lime	3413
Lansing - Kansas City	3433
Base Kansas City	3641
Marmaton	3680
Conglomerate	3708
Viola	3730
Simpson	3782
Arbuckle	3842

DST #1 - 3575-95 - Open 1½ Hours. Weak blow 76 minutes. Intermittant blow 14 minutes. Shut in 20 minutes. Recovered 75<sup>+</sup> Muddy water with few specks oil. BHP 990#

DST #2 - 3841-45 - Open 1 hour. weak blow 50 minutes, then died. Recovered 60<sup>+</sup> water. 45<sup>+</sup> oil cust mud. Shut in 20 Minutes BHP 1100#.

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Beardmore

Subscribed and sworn to before me this 12th day of August, 1953.

Leonard P. Tolle

My Commission Expires:  
January 28, 1956

