

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County, Sec. 28 Twp. 22 Rge. 13 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner H-30, Inc.
Lease Name Cossman Well No. 1
Office Address 200 North Main, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 18, 1964
Application for plugging filed April 18, 1964
Application for plugging approved April 18, 1964
Plugging commenced April 18, 1964
Plugging completed April 18, 1964
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,925 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	286'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 280 feet. Set bottom plug at 280 feet and cemented with 25 sacks cement and 1/3 sack hulls. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40 feet and cemented with 10 sacks cement and hulls, 2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1964

4-22-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Garnet B. Douthit (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Garnet B. Douthit
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 19 64

My commission expires December 3, 1964.
Geraldine Hays Notary Public.



KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **H-30, Inc.**

SEC. **23** T2S R. 13W
 LOC. **N2 NE 1/4**

FARM **Cossman** NO. **1**

COUNTY **Stafford**
KANSAS

TOTAL DEPTH **3,925'**
 COMM. **4-9-64** COMP. **4-18-64**
 SHOT OR TREATED
 CONTRACTOR **H-30, Inc.**
 ISSUED



CASING
 20 10
 15 8 5/8" 28.5' COM W/225 SX
 12 6
 13 5

ELEVATION **1901 OR**
1904 OF
1906 KB
 PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	15
Sand	255
Shale	285
Red Bed	760
Anhydrite	783
Shale	1200
Shale & Red Bed	1675
Line & Shale	2735
Shale	2760
Line & Shale	3010
Shale & Line	3110
Line & Shale	3435
Line	3635
Cherty Linn	3760
Line, Sand & Chert	3838
Chert	3855
Chert & Arbuckle	3915
Arbuckle	3925
Rotary T. D.	3925

<u>Sample Tops</u>		
Anhydrite Top	760	-2146
Anhydrite Base	783	-2118
Heshner	3904	-1378
Brown Line	3433	-1927
Lansing	3455	-1550
Viola	3752	-1846
Simpson	3825	-1931
Arbuckle	3875	-1767
Rotary T. D.	3925	-2017

RECEIVED
 STATE CORPORATION COMMISSION

APR 22 1964

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that the above and foregoing is a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Garnet B. Lovelitt

STATE OF KANSAS }
 } SS:
 SALONICK COUNTY }

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 21st day of April, 1964.

Geraldine Hays
 Geraldine Hays, Notary Public

My Commission Expires:
 December 3, 1964.