

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-21,278-0000

LEASE NAME RUTH WALLS "A"

WELL NUMBER #1

2970' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 28 TWP. 22S RGE. 13 (XX) or (W)

COUNTY STAFFORD

Date Well Completed 4-27-81

Plugging Commenced 7-15-91

Plugging Completed 7-15-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L. D. DRILLING, INC.

ADDRESS R.R. 1 Box 183 B Great Bend, KS. 67530

PHONE#(316) 79-3051 OPERATORS LICENSE NO. 6039

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 12, 1991 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? na

Producing Formation arbuckle Depth to Top _____ Bottom T.D. 3858'

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	294'	none
				4 1/2"	3857'	2000'

AUG 30 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Sanded bottom to 3400' - put 4 sacks of cement on top of sand fill up.

Mix 4 sacks hulls, 10 sx. gel, 50 sx. 60/40 cement, 10 gel, 1 sack hulls, 1-8 5/8" plug

100 sacks cement, 6% gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Saturn Well Service License No. 3641

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis

(Employer or Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) L. D. Davis


(Address) L. D. Davis
R.R. 1 Box 183 B Great Bend, KS
67530

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 91

Bessie M. DeWerff
Notary Public

My Commission Expires: 5-20-93

Bessie M. DeWerff



DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR

L. D. DAVIS - OPERATOR

RUTH WALLS "A" 1
SE SE NE
Sec. 28-22-13
Stafford Co., Ks.

ELEV. 1906 K.B. (adjusted for fill)
T. D. 3858'

COMMENCED: 4-20-81
COMPLETED: 4-27-81

CASING

3 5/8" set at 294'
4 1/2" set at 3857' (1' off bottom)

CEMENT

W/280 sx. 50/50 Pozmix, 2% Gel, 3% CC
W/175 sx. Cement, 18% Salt Sat.
3/4 of 1% CFR-2

FORMATION

DEPTH

Sand	0 - 69
Sand & Shale	69 - 296
Red Bed	296 - 765
Anhy.	765 - 790
Shale & Shells	790 - 1060
Shale & Lime	1060 - 1565
Lime & Shale	1565 - 3858
R.T.D.	3858

FORMATION TOPS

LOG

Anhy.	765
Heebner	3275
Toneka	3297
Douglas	3313
Brown Lime	3407
Lens. K/C	3427
Base K/C	3650
Cong.	3684
Viola	3714
Simpson	3796
Simp. Sand	3812
Arb.	3847
LOG T.D.	3849

AFFIDAVIT

STATE OF KANSAS)
) ss
COUNTY OF BARTON

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.



Don Popp

Sworn to and subscribed before me this 30th day of April, 1981.

My appointment expires 5-20-81

JUL 12 1990



Bessie M. DeWerff, Notary Public

BESSIE M. DEWERFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 5-20-81