

RECEIVED
STATE CORPORATION COMMISSION

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

APR 16 1982

WELL PLUGGING RECORD

Give ALL INFORMATION COMPLETELY
Make Requirements Affidavit

COUNTY Stafford SEC. 28 TWP. 22S RGE. 13W E/W
Location as in quarters or footage from lines:
NE NE SE

Lease Owner L.D. Drilling, Inc.

Lease Name Walls B-1 Well No. _____

Office Address Route 1 Box 183-B Great Bend, Ks. 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 3-31-82

Plugging completed 4-8-82

Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation _____ Depth to top _____ bottom T.D. 3857'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	280'	none
				4-1/2"	3906'	3001'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pumped in 20 sacks of common cement and pushed bottom plug to 3450', shot casing @2989'
and pulled a total of 78 joints of 4-1/2" casing. Plugged well with 5 sacks hulls,
25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 82

My Commission expires:



Irene Hoover
Notary Public.

15-185.00101-0000

Give All Information Carefully
State Where and When

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor

Section 28, Twp. 22S, Rge. 13W
Location: NE NE SE

Drilling Commenced: September 11, 1952
Drilling Completed: September 21, 1952

County: Stafford County, Kansas
R.T.D.: 3857'

Casings: 8 5/8" @ 280' w/V5 sax

Production: D & A

Figures below indicate bottom of formation:

30	Surface soil
265	Sand & Clay
280	Shale
550	Red Bed
756	Red Bed & Shells
783	Anhydrite
1420	Shale & Shells
3247	Shale & Lime
3281	Lime
3414	Lime & Shale
3670	Lime
3705	Lime & Shale
3756	Lime
3770	Chert
3835	Shale
3855	Shale & Lime
3857	Lime
3857	R.T.D.

Tops:

Maebner:	3281 (-1369)
Brown Lime:	3414 (-1502)
Lensing:	3434 (-1522)
Arbuckles:	3850 (-1938)

DST #1, 3438-65, open 30 mins., rec. 10'
mud, 220# BHP.
DST #2, 3539-62, open 30 mins., rec. 10'
mud, 230# BHP.

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1982

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W. W. Fisher

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 26th day of September, 1952.

Christina Thomas
Notary Public

My commission expires: October 13, 1954.

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 22 T. 22 R. 13
BOOK PAGE 16 LINE 40

STATE OF KANSAS COUNTY OF _____ (employee of owner) ~~XXXXXX~~ of the above-mentioned well, certify that the facts, statements, and matters herein contained and the log of

W. W. Fisher