


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 28 Twp. 22 Rge. 13 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Petroleum, Inc.
Lease Name Walls 'B' Well No. 1
Office Address 305 East Third, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 21, 19 52
Application for plugging filed September 21, 19 52
Application for plugging approved September 21, 19 52
Plugging commenced September 21, 19 52
Plugging completed September 21, 19 52
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3857 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 270' and set wooden plug at 270'.

Cemented and displaced through drill pipe 20 sacks cement on to plug at 270'. Mudded up to 35' and set second wooden plug. Placed 1/2 sack hulls on top of plug at 35'. Filled hole to bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R. R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher
305 East Third, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of September, 1952

My commission expires October 13, 1954

Charlotte Westman Notary Public.

24-2675-S 2-52-20M

PLUGGING
FILE SEC. 28 T. 22 R. 13 E
BOOK PAGE 46 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
SEP 29 1952
CONSERVATION DIVISION
Wichita, Kansas
9-29-52

DRILLER'S LOG WALLS 'B' NO. 1

Petroleum, Inc., Operator
Garvey Drilling Company, Contractor

Section 28, Twp. 22S, Rge. 13W
Location: NE NE SE
County: Stafford County, Kansas
R.T.D.: 3857
Production: D & A

Drilling Commenced: September 11, 1952
Drilling Completed: September 21, 1952
Casings: 8 5/8" @ 280' w/75 sax

Figures below indicate bottom of formation:

30 Surface soil
265 Sand & Clay
280 Shale
550 Red Bed
756 Red Bed & Shells
783 Anhydrite
1420 Shale & Shells
3247 Shale & Lime
3281 Lime
3414 Lime & Shale
3670 Lime
3705 Lime & Shale
3756 Lime
3770 Chert
3835 Shale
3855 Shale & Lime
3857 Lime

3857 R.T.D.

Tops:

Heebner: 3281 (-1369)
Brown Lime: 3414 (-1502)
Lansing: 3434 (-1522)
Arbuckle: 3850 (-1938)

DST #1, 3438-65, open 30 mins., rec. 10'
mud, 220# BHP.
DST #2, 3539-62, open 30 mins., rec. 10'
mud, 230# BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By ww Lick

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 26th day of September, 1952.

My commission expires: October 13, 1954.

REC Charlotte Therman
STATE CORPORATION COMMISSION

SEP 29 1952
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILED SEP 27 1952
BOOK PAGE 6 LINE 46