

15,053,20118.00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME E. Soukup #1

WELL NUMBER _____

SPOT LOCATION NE NE NW

SEC. 29 TWP. 14 RGE. 10W(E) or

COUNTY Ellsworth

Date Well Completed _____

Plugging Commenced 5/31/84

Plugging Completed 6/5/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR L.G. Stephenson & Co., Inc.

ADDRESS 7701 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-0531 OPERATORS LICENSE NO. # 5462

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 2915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	196'	none
				4 1/2"	2914'	1974'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 2750' & 4 sacks cement. Shot pipe at 2188', 2106', and 1974'. Pulled 61 joints. Plugged well with 4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, plug, & 100 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing pulling License No. 6050

Address Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

JUN 08 1984

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 7th day of June, 1984

 IRENE HOOVER
State of Kansas
My Comm. Exp. Aug. 15, 1985

Irene Hoover
Notary Public

My Commission expires _____

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

WELL LOG

15.053.20118.00.00

Company **Dreiling & Borell** Sec. 29 Twp. 14 Rng. ~~11~~¹⁰ *JD Kce*
 Route 2, Victoria, Kansas 67671
 Farm **Soukup** No. 1 Location **NE NE NW**
 Total Depth **2915'** County **Ellsworth**
 Comm. **1-22-70** Comp. **1-28-70** Elevation: **1642'** K. B.
 Contractor **L. J. Dreiling & Sons, Inc.** **1639'** D. F.
 Victoria, Kansas 67671 **1637'** G. R.
 Casing Record Cement Record Production:
196' - 8 5/8" **150 sacks cement**
2914' - 4 1/2" **100 sacks common salt saturated**
cement with 10 bbls. salt flush
ahead of cement

Figures Indicate Bottom of Formations

0'	20'	Sand
20'	210'	Shale
210'	280'	Sand
280'	300'	Hard Sand
300'	451'	Hard Sand
451'	488'	Anhy.
488'	1175'	Shale
1175'	2816'	Shale & Lime
2816'	2915'	Lime
2915'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Soukup #1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 30th day of January 1970.

JOSEPH A. HESS
NOTARY PUBLIC
My commission expires: September 19, 1970

Joseph A. Hess

JOSEPH A. HESS NOTARY PUBLIC STATE CORPORATION COMMISSION

RECEIVED
MAY 31 1984
CONSERVATION DIVISION
Wichita, Kansas