

15.053.00210.00.00

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Ellsworth County. Sec. 31 Twp. 17 Rge. 9 ~~XXX~~ (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NE

Lease Owner. Crowe Drilling Co., Inc.

Lease Name. Schroeder Well No. 1

Office Address. 323 W-K-H Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed. September 3 19 48

Application for plugging filed. September 3 19 48


Application for plugging approved. September 3 19 48

Plugging commenced. September 4 19 48

Plugging completed. September 4 19 48

Reason for abandonment of well or producing formation. Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. G. D. Stough

Producing formation. Depth to top. Bottom. Total Depth of Well. 3291 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Dakota Sand	Water	160'	174'	8 5/8" OD	201	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from 200 feet to 140 feet for each plug set.

Hole was filled with 15# mud to bottom of surface pipe.
 15 Sacks Cement pumped on top of Mud.
 5 Sacks Cement Pumped on top of hole.

9-8-48
 STATE OF KANSAS
 SEP 10 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crowe Drilling Company, Inc.
 Address. 323 Wheeler Kelly Haggy Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
 L. C. Crowe (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *L. C. Crowe*

323 W-K-H Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of September, 19 48.

Laura Pearl Bedinger
 Notary Public.

My commission expires January 30, 1950



15.053.00210.00:00

SCHROEDER #1

31-17-9

Ellsworth County
Kansas

Surface Casing

200'	
Ø - 140'	Shale
140 - 174'	Sand
174 - 200'	Shale & Lime Shells
200 - 245'	Shale & Shells
245 - 285'	Sand
285 - 295'	Pyrite
295 - 320'	Shale
320 - 470'	Red Bed, Shale & Shells
470 - 500'	Anhydrite, Sandy Lime
500 - 725'	Shale - Shells
725 - 785'	Shale
785 - 845'	Sand
845 - 935'	Shale
935 - 1150'	Sale, Shale & Shells
1150 - 1225'	Shale-Shells
1225 - 1280'	Lime
1280 - 1300'	Shale - Shells
1300 - 1470'	Shells & Shale
1470 - 1505'	Shale
1505 - 1580'	Lime & Shale
1580 - 1704'	Lime & Shale
1704 - 1805'	Shale & Shells
1805 - 1925'	Shells & Shale
1925 - 2000'	Lime & Shale
2000 - 2180'	Lime & Shale
2180 - 2310'	Shale - Streaks Lime
2310 - 2410'	Lime & Shale
2410 - 2480'	Shale & Lime
2480 - 2498'	Shale
2498 - 2590'	Lime
2590 - 2655'	Lime & Shale
2655 - 2740'	Lime
2740 - 2885'	Lime & Shale
2885 - 2935'	Shale - Lime
2935 - 3240'	Lime
3240 - 3256'	Shale & Lime
3256 - 3265'	Conglomerate
3265 - 3270'	Lime & Shale
3270 - 3276'	Lime
3276 - 3291'	Arbuckle
3291 -	Total Depth

C E R T I F I C A T I O N

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, L. C. Crowe, President of Crowe Drilling Company, Inc., hereby certify that the foregoing is a true and correct statement of drilling depths and formations of the above captioned well.

L. C. Crowe
L. C. Crowe

Subscribed and sworn to before me this 7th day of September, 1948.

Laurena Pearl Redinger
Notary Public

My commission expires January 30, 1950.

PLUGGING
FILE SEC-31-17-89a
BOOK PAGE 54 LINE 29

9-8-48

SEP 10 1948

NOTARY