

15.053.30126.00.00

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ellsworth County. Sec. 9 Twp. 16S Rge. (E) 8 (W)
Location as "NE/CNW'SW" or footage from lines AD. C SE NE
Lease Owner Will P. Ash
Lease Name WESTERMAN Well No. 1
Office Address 7802 East Indianapolis, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 21, 19 67
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced January 21, 19 67
Plugging completed January 21, 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Don Truan)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3015 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	230'	8-5/8"	1/16/67	-----
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 220 Feet; 1/2 sack Hulls, 25 sacks Cement and Plug through Drill Pipe; Heavy Mud to 40 Feet; 1/2 sack Hulls, 10 sacks Cement and Plug to Base of Cellar; 2 sacks Cement in Rat Hole. Job completed at 9 P.M.

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1967

CONSERVATION DIVISION
Wichita, Kansas

1-26-67

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Lawrence F. Gray of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of January, 19 67

Louise F. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

15.053.30126.00.00

DRILLERS LOG

WESTERMAN NO. 1

CASING RECORD:	COMPANY:	Will P. Ash	DESCRIPTION:
8-5/8" @ 230' w/130 sax cement	CONTRACTOR:	Sage Drilling Co.	Ap. C SE NE Sec. 9-16S-8W Ellsworth County, Kansas
TOTAL DEPTH: 3015'	COMMENCED:	January 16, 1967	
	COMPLETED:	January 21, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Red Bed	0	150	
Yellow Shale	150	175	
Red Bed	175	230	
Blue Shale	230	320	
Shale	320	372	
Anhydrite	372	390	
Shale	390	1104	
Shale & Lime	1104	1465	
Lime & Shale	1465	2270	
Shale & Lime	2270	2425	
Lime & Shale	2425	2520	
Shale & Lime	2520	2597	
Lime & Shale	2597	2685	
Lime	2685	2797	
Lime & Shale	2797	3015	

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 26 1967
 CONSERVATION DIVISION
 Topeka, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
 Lawrence F. Gray

Subscribed and sworn to before me this 25th day of January, 1967.

Louise K. Whitted
 Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.