

15.053.01233.00.00

DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Co
CONTRACTOR: Westgate Drilling Corporation
FARM: SW NW NE Sec. 34-17S-8W,
Ellsworth County, Kansas
COMMENCED: September 12, 1952
COMPLETED: September 24, 1952
ELEVATION: 1791 DF

0	to	160	Sand and shale
160	to	223	Shale and shells
223	to	390	Shale and sand
390	to	630	Red bed and shale
630	to	665	Shale
665	to	680	Anhydrite-shale
680	to	1060	Shale and shells
1060	to	2790	Lime and shale
2790	to	2830	Lime
2830	to	2833	Lime and shale
2833	to	2837	Brown lime
2837	to	2865	Shale
2865	to	3155	Lime
3155	to	3178	Lime and shale
3178	to	3200	Conglomerate
3200	to	3223	Lime and shale
3223	to	3231	Cherty Conglomerate
3231	to	3267	Conglomerate and shale
3267	to	3270	Conglomerate
3270	to	3310	Arbuckle
		3310	T. D. (RB)

Set 215 feet of 8 5/8" 26# surface pipe. Cemented with 135 sacks cement.

TOPS: Anhydrite 663 Lansing 2855 Arbuckle 3268
Heebner 2711 Cherty Cong 3221
Brown Lime 2831 Simpson 3241

DRILL STEM TESTS: 2876-2893, 1 hr, rec. 30' gas cut mud, 150' gas, 60# BHP.
#2 3268-77, 1 hr, 2050' gas cut sl. water scum oil, 970# BHP, FFP 855#.
#3 3283-3300, 1 hr, 2240' sul. water, 1020# BHP, FFP 1020#.

Cored 3268-77 and 3279-3310.
Schlumberger run
DRY, PLUGGED AND ABANDONED

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Rolfs #1, SW NW NE Section 34-17-8W, Ellsworth County, Kansas as reflected by files of the Westgate Drilling Corporation.

SEP 30 1952
CONSERVATION DIVISION

Harold A. Burt
Harold A. Burt

Subscribed and sworn to before me, a Notary Public within and for Sedgwick County, Kansas, this 29th day of September 1952.

Esther Unsell
Esther Unsell, Notary Public

My commission expires May 25, 1953.

PLUGGING
FILE SEC 34-17-8W
BOOK PAGE 42 LINE 41