


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15.053.00202.00.00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellsworth

County. Sec. 32 Twp. 16S Rge. 10 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE NE SW
Lease Owner Twyllah O. Gaskill
Lease Name Vlcek Well No. #1
Office Address 308 Springer Bldg., 6th & Cincinnati, Tulsa 19, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-20 19 61
Application for plugging filed 12-20 19 61
Application for plugging approved 12-20 19 61
Plugging commenced 12-20 19 61
Plugging completed 12-20 19 61
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Cecil Jones
Producing formation Depth to top Bottom Total Depth of Well 3393 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	304'	8 5/8"	304'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud
20 sack cement plug at 250'
10 sack cement plug at 35'
10 sack cement plug at 5' below ground level.

12-28-61
RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Box 127 Sterling, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Clark T. Snider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clark T. Snider

526 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of December, 19 61

My commission expires January 14, 1962

Frances O. Erhard

Notary Public.

15.053.00202.00.00

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG - - - - - VLCEK #1
Located: SE NE SW Section 32-16S-10W Ellsworth County, Kansas

OWNER: Twyllah O. Gaskill
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 12-12-61
COMPLETED: 12-20-61

ROTARY TOTAL DEPTH: 3393'

LOG

0 - 314 Shale & Red Bed
314 - 654 Shells, Shale & Red Bed
654 - 720 Anhydrite
720 - 900 Shale & Shells
900 - 1310 Shale, Shells & Salt
1310 - 1545 Shale & Lime
1545 - 2175 Lime
2175 - 2410 Shale & Shells
2410 - 2610 Shale & Lime
2610 - 2985 Lime
2985 - 3020 Shale
3020 - 3335 Lime
3335 - 3393 Conglomerate & Arbuckle T.D.

CASING RECORD

Set 8 5/8" Surface Casing
@ 311' with 200 sacks
Quick Set Cement.

Plugged & Abandoned

RECEIVED
STATE CONSERVATION COMMISSION

DEC 28 1961

CONSERVATION DIVISION
Wichita, Kansas