


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

PAWNEE County. Sec. 31 Twp. 22 Rge. (E) 19 (W)  
Location as "NE/CNW%SW%" or footage from lines NW NW SE  
Lease Owner GABBERT-JONES DRILLING COMPANY  
Lease Name KUEELD Well No. 1  
Office Address 514 ORPHEUM BUILDING - WICHITA  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 6-1 19 55  
Application for plugging filed 6-1-55 (PHONE) LETTER 6-4 19 55  
Application for plugging approved (PHONE) 6-1-55 19  
Plugging commenced 6-1-55 19  
Plugging completed 6-1-55 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well WARREN HORNER  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4909 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	226'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO SURFACE. PUMPED 85 SACKS CEMENT INTO SURFACE PIPE WITH PUMP TRUCK OF GLOBE OILWELL CEMENTING COMPANY.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 10 - 1955  
CONSERVATION DIVISION  
WICHITA, KANSAS

6-8-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES DRILLING COMPANY  
Address 514 ORPHEUM BUILDING, WICHITA

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall  
514 Orpheum Bldg (Address)

SUBSCRIBED AND SWORN to before me this 6TH day of JUNE, 19 55

My commission expires 12-31-56

Joan R. Fenton  
Notary Public.

PLUGGING  
RFR SEC 31 T 22 R 19W  
BOOK PAGE 124 LINE 11


**GABBERT-JONES DRILLING COMPANY**  
**WICHITA, KANSAS**  
**DRILLERS WELL LOG**

KUFELD #1  
 NW NW SE, SEC. 31-22-19W  
 PAWNEE COUNTY, KANSAS  
 COMMENCED 5-13-55  
 COMPLETED 6-1-55

DEPTH		FORMATION	REMARKS
FROM	TO		
0	190	SAND AND GRAVEL	
190	226	SHALE	RAN 226' OF 8 5/8" CASING, CEMENTED W/125 SACKS CEMENT.
226	590	SHALE & SHELLS	
590	660	SAND	
660	1320	SHALE & SHELLS	
1320	1367	ANHYDRITE	
1367	1600	SHALE & SHELLS	
1600	2280	SHALE & LIME	
2280	2785	LIME	
2785	3160	SHALE & LIME	
3160	3200	LIME	
3200	3315	LIME & SHALE	
3315	3390	LIME	
3390	3605	SHALE & LIME	
3605	4429	LIME	
4429	4465	LIME & SHALE	
4465	4485	LIME	
4485	4512	CHERT	
4512	4585	CHERTY LIME & SHALE	
4585	4590	SAND	DST 4585'-90', RECOVERED 135' SALT WATER BPH 1280#
4590	4909	LIME	
4909	TD		DRY AND ABANDONED

EXECUTED THIS 4TH DAY OF JUNE, 1955

C. L. Dobbet



STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 4 DAY OF June, 1955 PERSONALLY APPEARED C. L. Dobbet TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 11-19-58

Samuel E. Hall  
 NOTARY PUBLIC

