

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Hodgeman County. Sec. 30 Twp. 22 Rge. 25 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Rex & Morris, Etal

Lease Name King Well No. 1

Office Address Box 334, El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Feb. 23 19 57

Application for plugging filed " 19 "

Application for plugging approved " 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4820' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	495'	8 5/8"	490	None
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled to 400' with mud; Pumped down 20 sacks of cement at 400'; Filled with Rotary mud to 40'; Bridged hole at 40' and cemented with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rex & Morris Drilling Company

Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss. C. E. McClure (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure
Box 334, El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 57

My commission expires July 23, 1960
Winifred E. Gruit
Winifred E. Gruit Notary Public.

MAR 6 - 1957
CONSERVATION DIVISION
Wichita, Kansas

3-6-57

PLUGGING
FILE SEC 30 T 22 R 25W
BOOK PAGE 143 LINE 5

Elevation 2547 DF
2550 RB

KING WELL # 1

AURORA GASOLINE CO. - ET AL

Total Depth - 4820
Contractor - Rex & Morris Drilling Co.
Commenced - 2-7-57
Completed - 2-23-57
Initial Production - D & A

Location - NE NE NE
Section - 30-22S-25W
Hodgeman County, Kansas

Casing Record:
8 5/8" @ 495' w/ 300 sacks

FORMATION	DEPTH
Surface Hole	495
Shale	925
Red beds	1430
Shale & Shells	1750
Shale & Lime	1910
Shale & Shells	1935
Lime & Shale	2080
Shale & Salt	2300
Lime & Shale	3045
Shale & Lime	3095
Lime & Shale	3503
Shale & Lime	3590
Lime	3732
Lime & Shale	3830
Lime	3902
Lime & Shale	3972
Shale & Lime	4038
Lime	4155
Lime & Shale	4200
Lime	4439
Lime & Shale	4469
Lime	4567
Lime & Shale	4640
Lime	4689
Lime & Shale	4694
Conglomerate	4716
Lime	4720
Cherty Lime	4735
Lime	4820 TD

Ran Halliburton Guard Log

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

RECORDED
STATE CORP. RECORDS
MARCH 1957

Rex & Morris Drilling Company

By Paul S. Kountz

Title Geologist

STATE OF KANSAS)
COUNTY OF BUTLER)

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me, a Notary Public, this 5 day of March 1957.

PLUGGING
SEC. 30 T. 22 R. 25W
BOOK PAGE 143 LINE 5

Winfred E. Overt
Notary Public

My commission expires: July 23, 1960