

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

HODGEMAN County, Sec. 10 Twp. 22S Rge. (E) 24 (W)

Location as "NE/CNW/SE/SW" or footage from lines NW NE

Lease Owner THUNDERBIRD DRILLING, INC.

Lease Name MCNAIR "C" Well No. 1

Office Address 4328 E. Kellogg, Wichita, Kansas 67218

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed DRY HOLE 19

Application for plugging filed 6/6/ 1973

Application for plugging approved 6/6/ 1973

Plugging commenced 6/6/ 1973

Plugging completed 6/6/ 1973

Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS

Producing formation Depth to top Bottom Total Depth of Well 4745 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay, sand and shale		0	563	8 5/8	563	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 600' w/70 sx cement
2nd Plug and bridge to hold Kelly @ 40' w/10 sx cement
Hole plugged and abandoned at 9:30 PM 6/6/1973

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1973
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor GABBERT-JONES, INC. (If additional description is necessary, use BACK of this sheet)


Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. GABBERT-JONES, INC. (employee of owner) or ~~POWER BY OWNER~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James S. Sutton, 830 Sutton Place, Wichita, Ks.

11 day of July, 1973 (Address)



Marjorie Hall Notary Public

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

MCNAIR "C" #1
 NW NE, Section 10-22S-24W
 Hodgeman County, Kansas

Commenced: May 21, 1973
 Completed: June 6, 1973

OPERATOR: THUNDERBIRD DRILLING, INC.

Depth		Formation	Remarks
From	To		
0	130	Surface clay-sand-shale	Ran 13 jts dble used 28# 8 5/8"
130	570	Shale-sand	csg. set @ 563' centralizer on
570	1150	Shale-redbed	bottom jts cemented w/285 sks
1150	1195	Shale	common, 3% CC, 2% Gal Cement Circ.
1195	1395	Sand	P.D. @ 11:30 PM 5/21/1973
1395	1717	Shale	
1717	1760	Anhydrite	
1760	2045	Shale-lime stks	
2045	2180	Shale	
2180	2470	Shale-Lime	
2470	3038	Lime	
3038	3300	Lime-Shale	
3300	4015	Shale-Lime	
4015	4500	Lime	
4500	4535	Shale-Lime	
4535	4745	Lime	
4745	TD		Dry and Abandoned

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 12 1973
 CONSERVATION DIVISION
 Wichita, Kansas


I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the NW NE, Section 10-22S-24W, Hodgeman County, Kansas to the best of my knowledge and belief.

James S. Sutton, II
 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 12th day of June, 1973, personally appeared James S. Sutton, II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall
 Marjorie Hall, Notary Public