

15.145.20565.0000

12-6-02
RECEIVED

LEC 06 2002

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 207E
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-145-20,565 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Glenwood Resources, Inc. KCC LICENSE # 3972
(owner/company name) (operator's)

ADDRESS 3440 Youngfield St. #278 CITY Wheat Ridge

STATE CO ZIP CODE 80033 CONTACT PHONE # (303) 278-9282

LEASE Rugge WELL# 1 SEC. 26 T. 22S R. 19 (East/West)

C - SW - SE - SPOT LOCATION/0000 COUNTY Pawnee

660 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check one: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 326' CEMENTED WITH _____ SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4405' CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3974'-78', 4359'-63'

ELEVATION 2129/2124 T.D. 4407' PETD 4345' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Coral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off perms to 3925', dump 4 sks. cement on top of sand, shoot off casing, pull casing, bottom plug at 1250' - 50 sks., 2nd plug at 600' - 80 sks., 3rd plug at 40' - 10 sks., will use 60-40 poz cement, 6% gel
(if additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? _____

If not explain why? Not available

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Brad Seib PHONE# 785-798-7100

ADDRESS _____ City/State _____

PLUGGING CONTRACTOR Plains, Inc. KCC LICENSE # 4072

ADDRESS P.O. Box 346, Ness City, KS 67560 PHONE # 785 798-3993
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (if known?) _____

PAYMENT OF THE PLUGGING FEE (K.S.A. 52-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-04-02 AUTHORIZED OPERATOR/AGENT: Brad Seib
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Glenwood Resources, Inc.
3440 Youngfield St. #278
Wheat Ridge, CO 80033

December 06, 2002

Re: RUGGE #1
API 15-145-20565-00-00
CSWSE 26-22S-19W, 660 FSL 1980 FEL
PAWNEE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888

Sincerely

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor