


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800-Bitting Building  
Wichita, Kansas

Stafford County, Sec. 36 Twp. 22 Rge. (E) 12 (W)  
Location as "NE/CNW/SW" or footage from lines NW NE SW  
Lease Owner Harry Connelly  
Lease Name Hays Well No. 1  
Office Address 1019 Central Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 10-10 1955  
Plugging completed 10-16 1955  
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	249	8 5/8"		
		0	3929	5 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Well was plugged back from 3936 to 3593 - filled w/ sand from 3593 to 3565 - dumped 5 sks cement - mudded hole and pumped in 100 sks cement - mudded from 50' to 15' - filled to top w/ 5 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License #296  
Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
RICHARD M. FOLEY (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Richard M. Foley  
702 WAVERLY DR. Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 29<sup>th</sup> day of November, 1955

My commission expires 12-19-55 Notary Public.

24-7866-5 3-53-20M

11-30-55



DRILLERS LOG

Operator- Harry Connally

Contractor- Adkins Drilling Company, Inc.

Lease Hayes No. 1 NW 7th Sec. 36-22-12W. Stafford County, Kansas.

Formation	From	To	Formation	From	To
Surface soil	0	15			
Sand & Shells	15	140			
Shale & Shells	140	160			
Shale & Hard shells	160	255			

Set 249' of 2 5/8" 5 rd thread surface pipe rotary table measurements cemented with 250 sacks common cement. 2% Ca Cl<sub>2</sub> stopped plug @ 232' cement circulated.

Cement and plug	224	249
Shale- shells and sand	249	265
Red bed and sand, str str	265	568
Argyrite	568	605
Shale & Shells	605	1080
Salt	1080	1350
Shale & Shells	1350	1683
Lime & Shale	1683	2180
Shale & Lime shells	2180	2580
Shale & Lime strata	2580	3055
Lime (broken) & Shale str	3055	3110
Lime & Shale	3110	3195
Shale & Lime	3195	3250
Lime & Shale	3250	3360
Lime	3360	3671

Cored 3671- 3714 43 ft. Arbuckle Line 3714 3730.

Total Depth 3730'

Set 5 1/2" 355 casing at 3729ft. cemented with 115 sacks of Pozzolo cement, plug pumped to 3637'

State of Kansas )  
County of Barton )

JIM ADKINS, deposes and says that the foregoing is a true and correct copy of the Drillers Log on the Hayes #1 to the best of his knowledge and beliefs.

*Jim Adkins*

Subscribed and sworn to before me this 10 day of January 1955.

*Pauline B. Adkins*  
Notary Public

My Commission expires

2-29-56

**PLUGGING**  
FILE SEC-26Y-22R-12W  
BOOK PAGE-8-LINE-25