

LEASE NAME T. Richardson

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
_____ Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR Hallwood Petroleum, Inc.
ADDRESS 4582 S. Ulster St. Pkwy, Suite 1700
Denver, Colorado 80237

SEC. 36 TWP. 22 RGE. 12 (NMM(W))
COUNTY Stafford

PHONE#(303) 850-6257 OPERATORS LICENSE NO. 3613

Date Well Completed 10-9-30

Character of Well Oil

Plugging Commenced 10-12-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-16-95

The plugging proposal was approved on _____ (date)
by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3604'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 13" | 981' | none |
| | | | | 10-3/4" | 2836' | none |
| | | | | 8-5/8" | 3253' | 750' |
| | | | | 6-5/8" | 3478 | 754' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Plugged bottom with sand to 3017' and 6 sacks cement. Shot 6-5/8" casing @1800', @1600' & 750'. Shot 8-5/8" at 748', @705', & @690'. Came free, pulled string. Shot 10-3/4" at 709' and 252'. Ran tubing to 650', pumped 260 sacks cement down tubing. Pulled tubing out of hole. Put in swage in 13-3/8" to 5-1/2" collar. Pumped 150 sacks of cement down hole... (60/40 6% gel). Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 25th day of October, 1995

[Signature]
Notary Public

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM



STATE CORPORATION COMMISSION
Wichita, Kansas
Revised 05-88

10-26-95