

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20625-0000

LEASE NAME Spangberg

WELL NUMBER #1

SPOT LOCATION 200' W of
NE NE SW

SEC. 33 TWP. 22 S RGE. 12 W (E) or (W)

COUNTY Stafford

Date Well Completed _____

Plugging Commenced 1-19-84

Plugging Completed 1-25-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Brougner Oil, Inc.

ADDRESS P.O. Drawer 1367 Gt. Bend, Kansas 67530

PHONE # (316) 793-5610 OPERATORS LICENSE NO. 6393

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3717'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	246'	none
				5-1/2"	3716'	2713'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3300' and ran 5 sacks cement. Shot casing @2900', 2713' and pulled a total of 67 joints (2713') of 5-1/2" casing. Plugged surface with 3 hulls, 20 gel, 50 cement, 5 gel, 1 hull, released plug and displaced with 100 cement, 60/40 pos, 2% gel, 3% ec. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

JAN 30 1984

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 27 day of January, 1984



Irene Hoover
Notary Public

My Commission expires: _____