


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Reno County, Sec. 6 Twp. 22 Rge. (E) 9 (W)  
Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner: Lario Oil & Gas Company  
Lease Name: Rose Well No. 1  
Office Address: 301 S. Market, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed December 2 19 59  
Application for plugging filed September 9 19 63  
Application for plugging approved September 10 19 63  
Plugging commenced October 6 19 63  
Plugging completed October 9 19 63  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production May 19 60  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Simpson Depth to top 3613 Bottom Open Hole Total Depth of Well 3621 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200'	None
				5 1/2"	3615'	3250'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Cleaned out cellar, set plug at 3600' and run 5 sacks of cement, worked 19" tension in 5 1/2" pipe, shot at 3225' and started pipe. Set plug at 230' rock bridge 230' to 220' run 25 sacks of cement from 220' to 145', mudded from 40' to base of cellar.

11-12-63

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1963

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.  
Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Leo Ross (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Leo Ross*  
301 S. Market, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November, 19 63

My commission expires June 28, 1964

*Th. Cummings*  
Notary Public.

LARIO OIL & GAS COMPANY  
 Rose No. 1  
 Cen. SW NE Sec. 6-22S-9W  
 Reno County, Kansas

Drilling Commenced: October 19, 1959  
 Drilling Completed: October 28, 1959  
 Well Completed: December 2, 1959  
 Drilling Contractor: Birmingham-Bartlett Drilling Co.  
 Total Depth - 3621'  
 I.P. - 8 bbls. oil plus 45 bbls. water (85%) 24 hour physical potential

CASING RECORD

8 5/8" 219.92 Set @ 200'  
 Cem. w/ 200 sacks  
 5 1/2" 3651.43' (o.a.) Set @ 3615'  
 Cem. w/ 75 sacks

Formation                      Depth

Clay	40
Sand	120
Red bed	347
Anhydrite	365
Shale & shells	1300
Lime & shale	1555
Lime	1820
Shale & lime	2530
Lime	2775
Lime & shale	2860
Lime	2980
Shale	3062
Lime	3450
Conglomerate	3458
Kinderhook	3460
Lime & shale	3528
Lime	3585
Lime, chert, shale	3605
Shale	3613
Sand	3621

GEOLOGICAL TOPS - R.B. MEAS.

Elevation	1751 R.B.
Heebner	2926 (-1175)
Brown Line	3062 (-1311)
Lansing	3091 (-1340)
Conglomerate	3428 (-1677)
Detrital Chert Zone	3448 (-1697)
Base Detrital Chert Zone	3458 (-1707)
Kinderhook	3458 (-1707)
Maquoketa	3480 (-1729)
Viola	3528 (-1777)
Simpson Shale	3605 (-1854)
Simpson Sand	3613 (-1862)
Rotary Total Depth	3616 (-1865)
Cable Total Depth	3621 (-1870)

11-6-59 Dowell fraced with 10,000 gallons  
 plus 15,000# sand

RECEIVED  
 STATE CORPORATION COMMISSION

SEP 10 1963

CONSERVATION DIVISION  
 Wichita, Kansas