

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Reno SEC. 6 TWP. 22S RGE. 9W E/W
Location as in quarters or footage from lines:
SE NW SW

Lease Owner Zenith DRilling Corporation
Lease Name Culber B #1 Well No. _____
Office Address Fourth Financial Center Suite 505 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 12-2-81
Plugging completed 12-4-81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ bottom T.D. 3645'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	242	none
				4-1/2"	3644'	3125'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 3550' and set 4 sacks cement. S hot pipe @3120 and
pulled a total of 74 joints. Plugged well with 4 sacks hulls, 25 sacks gel, 8-5/8" plug,
100 sacks 50/50 pos, 2% gel. Plugging completed.
12-9-81

RECEIVED
STATE CORPORATION COMMISSION

DEC - 9 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Kelso Casing Pulling CONSERVATION DIVISION
Wichita Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 81



Irene Hoover
Notary Public.

My Commission expires: _____

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 1980

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579CONSERVATION DIVISION
Wichita, KansasWELL LOG ----- CULVER "B" #1
Located: SE NW SW, Section 6-22S=9W, Reno County, KansasOWNER: Zenith Drilling Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling CompanyCOMMENCED: December 11, 1980
COMPLETED: December 18, 1980

TOTAL DEPTH: 3645'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 245 Sand and Clay	Ran 5 joints 8 5/8", 23# new casing. 230.97' pipe set at 242' K.B. Cemented with 200 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 6:45 PM, 12-11-80, by Howco.
245 - 376 Shale	
376 - 390 Anhydrite	
390 - 740 Shale	
740 - 3350 Lime and Shale	
3350 - 3455 Lime	
3455 - 3545 Lime and Shale	
3545 - 3645 Lime	Ran 87 joints 4 1/2", 9.5# OD casing. 3646' pipe set at 3644' K.B. Cemented with 125 sacks 50/50 Pozmix with 18% salt, 3/4 of 1% CFR-2 and 20 barrels salt flush ahead of cement. Plug down at 6:30 AM, 12-18-80.

Deviation Surveys: 1° at 1612'
2° at 3630'