


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Reno County, Sec. 6 Twp. 22S Rge. 9W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
450' FWL, 330' FSL, SW/4.  
Lease Owner Daskocil Sausage Company  
Lease Name Culver #1 Well No. 1  
Office Address 321 North Main St, South Hutchinson, Ks. 67505  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Dry Hole  
Date Well completed April 18, 1977 19  
Application for plugging filed April 18, 1977 19  
Application for plugging approved April 18, 1977 19  
Plugging commenced 3:00 PM, April 18, 1977 19  
Plugging completed 5:15 PM, April 18, 1977 19  
Reason for abandonment of well or producing formation

Dry Hole  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3177'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
40 sacks cement at 500';  
25 sacks at 200'; 10 sacks at 10';  
2 sacks in rathole.

4-21-77

APR 24 1977


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.  
F. A. Wuellner (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY  
(Signature) F. A. Wuellner  
F. A. Wuellner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 1977



CHARLES HALL—NOTARY PUBLIC  
My Commission Expires Jan. 6, 1978

Charles M. Hall  
Charles M. Hall, Notary Public.

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- CULVER #1  
Located: 450' FWL, 330' FSL, SW/4, Section 6-22S-9W,  
Reno County, Kansas

OWNER: Doskocil Sausage Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 14, 1977  
COMPLETED: April 18, 1977

TOTAL DEPTH: 3177'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 220 Sand, Red Shale	Ran 8 joints 8 5/8" casing, 198.89' set at 215' K.B. Cemented with 200 sacks cement with 2% gel and 2% cc. Plug down at 6:00 PM, 4-14-77.
220 - 1553 Shale	
1553 - 3177 Lime and Shale	Plugged.

RECEIVED  
MINERAL COMMISSION COMMISSIONER

APR 21 1977

COMMISSIONER D.V.S. CIV  
Wichita, Kansas