

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-185-01462-0000

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1963  
7-29-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Marty Hayes of Alpine Oil & Royalty Inc. has this date requested permission to plug the following described well:

Mr. Hayes guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Inc.

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name: Sundermeier Well No. # 1

Location: SE SW NW Sec. 7 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3925 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hayes was instructed to plug the well as follows:

297' of 8 5/8" surface pipe, cemented with 275 sacks.

Fill hole with mud to 240', 1st cementing plug, 1/2 sack

hulls, cement with 20 sacks. Fill hole with mud to 40'.

2nd cementing plug, 1/2 sack hulls, cement with 10 sacks

to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent