

15-155-00272-0001

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

October 17, 1967

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1967  
11-3-67  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ben Thompson of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mc Adams Pipe & Supply Co.

Complete Address: Drawer 960, Bristow, Oklahoma 74010

Lease Name: Wisby Well No. 1

Location: NE NE NE Sec. 18 Twp. 22 Rge. 9 (X) (W) X

County Reno Total Depth 3725' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Thompson was instructed to plug the well as follows:

Push 5 1/2" plug to 3600'. Fill hole with sand to 3590' and cement with 7 sacks. Fill hole with mud to 255'. Set rock bridge from 255' to 245' and cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

*William L. Mitchell*  
Conservation Division Agent