



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

November 10, 1970

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

11-18-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Pulling Co has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Lario Oil & Gas Company

Complete Address: 301 S. Market, Wichita, Kansas 67202

Lease Name: Homer Drake "B" Well No. 4

Location: C N/2 SE SE Sec. 18 Twp. 22 Rge. 9 (E) (W) X

County: RENO Total Depth 3631' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3600' and cement with 3 sacks cement.

Set rock bridge from 220' to 210'. Dump 5 sacks cement on bridge and

let set up. Bail hole dry. Cement hole with 20 sacks cement (total

25 sacks). Fill hole with mud to 40'. Set rock bridge from 40' to 30'

and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent