

State of Kansas



FORM - CP-8
Rev. 6-26-62

15-185-30090-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965
7-19-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Lawrence Gray of Circle Oil Company, Inc has this date requested permission to plug the following described well:

Mr. Gray guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Comapny, Inc.

Complete Address: 816 Bitting Bldg., Wichita, Kansas

Lease Name: Symns Well No. # 1

Location: SW NE SE Sec. 28 Twp. 22 Rge. 14 (E) (W) W

County Stafford Total Depth 3943' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Gray was instructed to plug the well as follows:

269' of 8 5/8" surface pipe, cement circulated with 250 sacks.
Fill hole with drilling mud to 250', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving