

State of Kansas

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1966

6-20-66

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Company has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.Operator's full Name: John C. GravesComplete Address: 412 Union Center, Wichita, KansasLease Name: Curtis Well No. # 1Location: SW SW SE Sec. 25 Twp. 22 Rge. 14 (E) (W) WCounty Stafford Total Depth 3870' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Miller was instructed to plug the well as follows:

365' of 8 5/8" surface pipe, cement circulated with 375 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving