



15-185-30202-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1965
(1-10-65)
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Company

Complete Address: 1532 Wichita Plaza, Wichita, Kansas

Lease Name: Lofland Well No. # 1

Location: SE SE SW Sec. 28 Twp. 22 Rge. 11 (E)(W) W

County Stafford Total Depth 3640' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Miller was instructed to plug the well as follows:

252' of 8 5/8" surface pipe, cement circulated with 310 sacks.
Fill hole with drilling mud to 240', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling mud
to 40', 2nd cementing plug, bridge with hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent