

State of Kansas



15-083-20099-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1969 10-27-69
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Burris of Chief Drlg., Co has this
date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Co. Inc.

Complete Address: Suite 905 Century Plaza, Wichita, Kansas

Lease Name: Hey Well No. 1

Location: SE NW Sec. 27 Twp. 22 Rge. 25 (E) (W)

County Hodgeman Total Depth 4064' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

8 5/8" to 331' circulated w/ cement . Mud 4064' to 600'

Spot 50 sacks cement 600' to 450' Mud 450' to 380'

Spot 25 sacks cement 380' to 280' Mud 280' to 40'

Plug, Halls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Lewis
Conservation Division Agent