

State of Kansas



FORM - CP-2  
Rev. 6-26-62

15-185-30397-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

7-16-64

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: Woody's Quality Oil Company

Complete Address: 1119 Cravens Bldg., Oklahoma City, Okla.

Lease Name: Krankenber Well No. # 1

Location: SE SW SE Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3775 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Curtis was instructed to plug the well as follows:

264' of 8 5/8" surface pipe, cemented with 225 sacks. Fill  
Hole with drilling mud to 250', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drill-  
ing mud to 40', 2nd cementing plug, bridge with hulls, and  
cement with 10 sacks to base cellar. Bridge and cement rat  
hole with 2 sacks.

Very truly yours,

*Archie Elving*