



15-185-30200-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 3 1965

CONSERVATION DIVISION  
Wichita, Kansas

11-3-65

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of Graves Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Co. & Graves Drlg., Co.

Complete Address: 1532 Wichita Plaza, Wichita, Kansas

Lease Name: Brensing Well No. # 1

Location: NE SW NW Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3760' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

264' of 8 5/8" surface pipe, cement circulated with 300 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*