



15-185-30199-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 11 1965
10-11-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Brooks Pierce of Donald T. Ingling has this
date requested permission to plug the following described well:

Mr. Pierce guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First National Bank Bldg., Wichita, Ks.

Lease Name: Curtis Well No. # 1

Location: C S/2 SE SW Sec. 19 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3782' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pierce was instructed to plug the well as follows:

260' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole
with drilling mud to 240', 1st cementing plug, bridge with hulls
and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with hulls, and cement with 10 sacks to
base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent