



15-185-20484-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 7 1974
CONSERVATION DIVISION
Wichita, Kansas
3-7-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Zimmerman of Woodman & Iannitti has this

date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc

Complete Address: 300 W Douglas Wichita, KS

Lease Name: Ukens H Well No. 1

Location: C N/2 NW/NW Sec. 22 Twp. 22 Rge. 12 (E)(W) W

County: Stafford Total Depth 3681 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

289 ft 8 5/8 surface cemented with 240 sacks. Pump plug,

40 sacks cement to 500 ft. 2nd plug at 250 ft, 30 sacks

cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks cement

to surface. 2 sacks cement in rat hole.

Pumped by Sun Cementing Co Great Bend, KS

Very truly yours,

Conservation Division Agent