



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 21 1973

CONSERVATION DIVISION  
Wichita, Kansas

11-21-73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Winn of O.A. Sutton has this

date requested permission to plug the following described well:

Mr. Winn guarantees payment of the plugging fee.

Operator's full Name: O.A. Sutton

Complete Address: 800 Sutton Place, Wichita, Kansas

Lease Name: Shriwise Well No. 1

Location: C SE SE Sec. 34 Twp. 22 Rge. 25 (E) (W)

County: Hodgeman Total Depth 4800' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Winn was instructed to plug the well as follows:

8 5/8" to 509' circulated w/ cement. Mud 4800' to 800'

Spot 115 sacks cement 800' to 400' Mud 400' to 45'

Plug, H<sub>4</sub>ills & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent